


Naval Air Station, Fallon

Work Plan for Investigation of Active Sites

Remedial Project Managers Meeting April 26, 2007

Eric C. Green
Remedial Project Manager
Naval Facilities Engineering
Command, Southwest

Location of Sites to be Investigated



04042007 NAS Fallon\SAFM\Challe_locations.mxd TEM-MO M.Hendey

Sites to be Investigated



➤ **Site 1 – Crash Crew Training Area**

- ✓ Burn pit, aboveground storage tanks (ASTs), pipeline (all removed)
- ✓ Contaminated soil and floating product, fuel and solvent contamination
- ✓ Several hundred cubic yards of contaminated soil has been removed
- ✓ Bioslurper pilot study from 1996 to 1998 removed 900 gallons of product

➤ **Site 2/4 – New Fuel Farm/Transportation Yard**

- ✓ Old fuel tanks have been filled with slurry
- ✓ Significant floating product at the site
- ✓ Soil removed at Site 4
- ✓ Groundwater affected by Site 2
- ✓ Pilot studies completed
- ✓ Residual vadose zone soil contamination remains in pockets at Site 2

Sites to be Investigated



➤ **Site 3 – Hangar 1 Area**

- ✓ Multiple sources of contamination, both fuel and solvent
- ✓ Groundwater contamination is the primary issue

➤ **Site 6 – Defuel Disposal Area**

- ✓ Off-specification fuel discharged to ground surface
- ✓ Two areas; only one appears to have been used for disposal
- ✓ Residual vadose zone contamination still present in central disposal area

➤ **Site 14 – Old Vehicle Maintenance Shop**

- ✓ Vehicle maintenance and hobby shop
- ✓ Floating fuel product and some solvents
- ✓ Residual vadose zone soil contamination

Sites to be Investigated



➤ **Site 16 – Old Fuel Farm**

- ✓ Four underground storage tanks (USTs) demolished
- ✓ Potential new source of solvent contamination identified
- ✓ Potential new source of fuel contamination identified through SCAPS
- ✓ Significant product contamination (mostly residual)
- ✓ Concerns about impacts to nearby drain

➤ **UST-R Site 1 (395)**

- ✓ Two USTs removed
- ✓ Floating fuel product identified

➤ **UST-R Site 2 (800 Complex)**

- ✓ Numerous USTs and ASTs removed
- ✓ Contamination detected in soil and water
- ✓ Monitoring wells previously located at this site were plugged

Summary of Previous Investigations



- Remedial Investigation completed for IR sites, 1994
- Engineering Evaluation and Cost Analysis (EE/CA) completed for many IR sites, 1995 and 1996
- Sampling during tank removal programs, 1992, 1995, and 1996
- Additional sampling in support of remedial design and remediation alternatives (bioslurping system, Site 1 soil removal)
- Sampling conducted for intrinsic remediation study, 2002
- Additional base investigations/LUST investigations

Primary Documents used for Planning Additional Investigation



- **Remedial Investigation, Oak Ridge National Laboratory, 1994**
- **Trend Analysis and Updated Plume Assessment, Battelle, 2003**
- **Data Summary and Recommendations Report, Battelle, 2003**
 - ✓ Report includes summary of intrinsic remediation sampling, EE/CAs, LUST program sampling, etc.
- **UST removal reports, including PRC 1993, IT 1995, WESTEX 1996**

Tasks Completed for Work Plan

(Results Presented in the Work Plan)



- **Passive soil gas sampling, September 2006**
 - ✓ Site 6, northern disposal area (no sources identified)
 - ✓ Site 16, solvent source near well MW-16-3 (localized solvent source identified)

- **Tier 1 human health evaluation (soil), February 2007**
 - ✓ Previous soil data adequate for most sites, potential risks identified at Sites 1, 14, and UST-R Site 2 (800 Complex)
 - ✓ Residual vadose zone contamination (TPH) not evaluated as part of risk assessment, some areas with concentrations above Nevada screening criteria

- **Ecological habitat survey, February 2007**
 - ✓ Viable habitat only identified at Sites 1, 2 (portions), 6, 16, and UST-R Site 2 (800 Complex)

- **SCAPS Investigation, February 2007**
 - ✓ Areas of product/smear zone identified, as well as potential new source at Site 16

Overall Goal



➤ **Minimize additional investigations**

- ✓ **Focus on recommendations from previous investigations**

- ✓ **Utilize new information from SCAPS**

- Sites 1, 2, 4, 14, 16, UST-R Site 1 (395), and UST-R Site 2 (800 Complex)
- Soil smear zones, floating product information

- ✓ **Standardize sampling locations and methods (groundwater)**

➤ **Perform judgmental sampling with field step-out criteria**

- ✓ **Allow for additional soil sampling based on:**

- Visual observations
- PID headspace readings

➤ **Provide strategy for accelerated cleanup and site closure**

- ✓ **Additional information from SCAPS investigation**

- Fuel fingerprinting
- Temporary wells - is product recoverable?

Investigation Objectives



➤ **Collect additional soil data**

- ✓ **Confirm results of SCAPS LIF response at critical areas**
- ✓ **Fill data gaps left over from SCAPS investigation**
- ✓ **Delineate potential soil smear zones**
- ✓ **Delineate surface soil and vadose zone contamination identified during previous investigations**
- ✓ **Evaluate potential risk to ecological receptors**
- ✓ **Update human health risk assessment**
- ✓ **Delineate areas for potential removal or remedial action**
- ✓ **Samples to be analyzed for TPH, VOCs, and PAHs (SIM Method)**
 - Selected samples also analyzed for geotechnical parameters for remedial design, soil vapor to indoor air modeling

Investigation Objectives



➤ **Collect additional groundwater data**

- ✓ **Update groundwater database using standardized methods and monitoring wells that comply with Nevada Revised Statutes 2005 Chapter 534**
- ✓ **Evaluate potential human health risks from groundwater and vapor intrusion**
- ✓ **Install new wells**
 - Wells needed to fill data gaps (previous sampling, SCAPS, soil gas results, Site 16 drain concerns)
 - Wells needed to replace existing, poor-quality wells
 - Additional sentry wells at Site 6
- ✓ **Focus on dissolved phase**
 - Plume stability
 - Trends in concentrations
- ✓ **Samples to be analyzed for TPH, VOCs, PAHs (SIM Method), and TDS**
 - Selected samples also analyzed for MNA parameters

Investigation Objectives



- **Install Groundwater Velocity Sensors**
 - ✓ Site 16
 - ✓ Site 6 (if possible)

- **Redevelop existing wells if needed prior to sample collection**
- **Survey all new locations**
- **Confirm old well locations**

Summary of Planned Investigation



- **Investigation planned for two 10 day rotations**
 - **Surface soil samples – 45**
 - **Subsurface soil samples – 71**
 - **New Monitoring wells – 25**
 - **Groundwater samples – 110**

- **Provision made for a second limited mobilization after review of initial data to fill any data gaps, if needed.**

Results of Additional Investigation



- **Summarize all results in RI addendum report**
- **Provide recommendations for removal/remedial actions**
- **Provide recommendations for regulatory framework to cover each site**

Schedule



- **Submit draft plan for state review: May 2007**
- **Submit final plan: June 2007**
- **Conduct field effort: July-August 2007**
- **Submit draft RI Addendum report: November 2007**