broadbentinc.com

July 21, 2025 Project No. 23-01-200

Alan Pineda, PE
Professional Engineer
Bureau of Industrial Site Cleanup
Nevada Division of Environmental Protection
375 E. Warm Springs Rd., Ste. 200
Las Vegas, NV 89119

Attn: Mr. Pineda

Re: Modification No. 7 to the Remedial Design Report

Hydro Pit Liner, Revision 1

Three Kids Mine, Henderson, Nevada

Dear Mr. Pineda:

Broadbent & Associates, Inc. (Broadbent) is pleased to submit this revised modification to the *Remedial Design Report, Revision 1* for the Three Kids Mine located in Henderson, Nevada.

Please do not hesitate to contact us if you should have any questions or require additional information.

Sincerely,

BROADBENT & ASSOCIATES, INC.

Kirk Stowers, CEM Principal Geologist

CC: JD Dotchin, NDEP

Joe McGinley, McGinley & Associates, Inc. Caitlin Jelle, McGinley & Associates, Inc. Ann Verwiel, ToxStrategies Robert Unger, Lakemoor Ventures LLC Mindy Unger-Wadkins, Lakemoor Ventures LLC Leo Drozdoff, Drozdoff Group, LLC Karen Gastineau, Broadbent & Associates, Inc. Christene Klimek, City of Henderson Sean Robertson, City of Henderson Stephanie Garcia-Vause, City of Henderson Anthony Molloy, City of Henderson Quincy Edwards, Pulte Group Doug Adair, Pulte Group Paul Kenner, on behalf of Pulte Group Michael Ford, Snell & Wilmer Brad Cahoon, Dentons Bryan Douglass, Douglass, Inc. Charles M. Damus, Laker Development, LLC Darryn Padfield, River Mountain Bike Shop David Grossheim, Laker Plaza, Inc. Frank Sator, Laker Development, LLC Laird Sanders, Lake Mead Boat Storage Rhonda Sanders, Lake Mead Boat Storage

Tyler Cahoon, Dentons

Modification No. 7 to the Remedial Design Report, Revision 1 Hydro Pit Liner, Revision 1 Three Kids Mine Henderson, Nevada

JURAT: I, Karen Gastineau, certify that I am responsible for the services in this document and for the preparation of this document. The services described in this document have been provided in a manner consistent with the current standards of the profession and to the best of my knowledge comply with all applicable federal, State, and local statutes, regulations, ordinances, and the requirements of the Mine Remediation and Reclamation Agreement and Administrative Order on Consent for the Three Kids Mine Site.

Karen Gastineau

Senior Hydrogeologist CEM #2468 (4/1/2027)

Karer Dastinear

Date

July 21, 2025



TECHNICAL MEMORANDUM

To: Alan Pineda, Nevada Division of Environmental Protection

From: Karen Gastineau, Broadbent & Associates, Inc.

Subject: Modification No. 7 to the Remedial Design Report

Hydro Pit Liner, Revision 1

Three Kids Mine Site, Henderson, Nevada

Date: July 21, 2025

This Technical Memorandum presents Modification No. 7 to the *Remedial Design Report, Revision 1* dated March 4, 2024 (Remedial Design Report) for the Three Kids Mine Site (Site) in Henderson, Nevada. This modification presents changes to the Hydro Pit liner design.

Hydro Pit Liner Redesign

The Hydro Pit liner design in the Remedial Design Report is depicted in Figure G-15, and Figure G-16 depicts the elevation with the two feet of cover as required by the Record of Decision (Nevada Division of Environmental Protection [NDEP] 2023). The original design conceptualized that the entire Hydro Pit would be filled with a tailings-waste rock mixture; however, the actual volume of tailings excavated and the waste rock required for compaction did not fill the Hydro Pit to its rim. Additionally, planned stormwater infrastructure previously included a detention basin over the Hydro Pit liner, but the future development's stormwater system no longer includes a detention basin over the Hydro Pit.

To allow for a thicker cover above the liner which will provide greater protection of the liner, a redesigned liner was created and presented herein. The lower liner elevation and increased cover thickness on top of the liner also allows for more flexibility with park design features for future development. The redesigned final grades over the Hydro Pit are depicted in GRD-1, the liner elevation is depicted in GRD-2, and six profiles of the backfilled Hydro Pit, liner, and cover are presented as PROF-1 through PROF-6. Figure G-17 from the Remedial Design Report was also revised to clarify the anchor trench design.

Attachments


GRD-1	Community Park C Grading Plan
GRD-2	Hydro Pit Liner Grading Plan
PROF-1	Hydro Pit Liner and Park Profile 1
PROF-2	Hydro Pit Liner and Park Profile 2
PROF-3	Hydro Pit Liner and Park Profile 3
PROF-4	Hydro Pit Liner and Park Profile 4
PROF-5	Hydro Pit Liner and Park Profile 5
PROF-6	Hydro Pit Liner and Park Profile 6


Figure G-17 (Rev 2) Hydro Pit Liner Details


A Responses to NDEP Comments


References

Broadbent. 2024. Remedial Design Report, Revision 1, Three Kids Mine, Henderson, Nevada. March 4. NDEP. 2023. Record of Decision, Three Kids Mine, Henderson, Nevada. September.









NO. DESCRIPTION DATE BY APP. APP. PP.


LAKEMOOR
HYDRO PIT LINER AND PARK PROFILI
EXHIBIT

DATE: 5/30/25

DRAFTER: EE


DESIGNER: EE

CHECKED: DY
PROJECT NO.
PUL2400



PROF-1
SHEET 3







PROF-2
SHEET 4

PROFILI

LINER AND PAR

PH

HYDRO

DATE: 5/30/25

DRAFTER: EE

DESIGNER: EE

CHECKED: DY

PROJECT NO.


PUL2400


EXHIBIT

LAKEMOOR

HORZ: 1" = 100'
VERT: 1" = 20'

SCALE - 1"=100'





DATE BY APP. WESTWOOD

Phone (702) 284-5300 5725 W. Badura Ave. Suite 100

Las Vegas, NV 89118

westwoodps.com

APP.				
APP. DATE				
ВУ				
DATE				
DESCRIPTION				
NO.				

LAKEMOOR
HYDRO PIT LINER AND PARK PROFILE 3
EXHIBIT


DATE: 5/30/25

DRAFTER: EE


DESIGNER: EE


CHECKED: DY
PROJECT NO.

PROJECT NO.
PUL2400



PROF-3
SHEET 5





SCRIPTION
DATE BY APP.

WESTWOOD Professional Services, Inc.

PROFILE 4


LAKEMOOR
HYDRO PIT LINER AND PARK
EXHIBIT

DATE: 5/30/25


DRAFTER: EE

DESIGNER: EE

CHECKED: DY
PROJECT NO.
PUL2400



PROF-4
SHEET 6



poo PROFILI LINER AND PAR LAKEMOOR **EXHIBIT** PH HYDRO


DATE: 5/30/25

DRAFTER: EE


DESIGNER: EE

CHECKED: DY
PROJECT NO.

PUL2400



PROF-5
SHEET 7



NO. DESCRIPTION DATE BY APP. WESTWOOD Professional Services, Inc.

LAKEMOOR
HYDRO PIT LINER AND PARK PROFILE
EXHIBIT

DATE: 5/30/25

DRAFTER: EE


DESIGNER: EE

CHECKED: DY

PROJECT NO.
PUL2400





PROF-6
SHEET 8




CONSTRUCTION NOTES


- 1. ZONE 1 MATERIAL SHALL BE PROCESSED OR NATURAL MATERIAL WITH 100% PASSING A ⅔ " SIEVE. NO CRUSHED STONE, PARTICLES MUST BE SUB—ANGULAR TO ROUNDED AND FREE OF ORGANICS AND DEBRIS OF ANY KIND. UNIFORMITY COEFFICIENT OF 1.9 TO 2.4 AND COMPACTED TO 95% PER ASTM D1557.
- 2. ZONE 3 MATERIAL SHALL BE PROCESSED OR NATURAL MATERIAL WITH 100% PASSING A 3 " SIEVE AND 100% RETAINED ON THE 1 " SIEVE. NO CRUSHED STONE, PARTICLES MUST BE SUB-ANGULAR TO ROUNDED AND FREE OF ORGANICS AND DEBRIS OF ANY KIND. UNIFORMITY COEFFICIENT OF 1.9 TO 2.4
- 3. THE CONTRACTOR SHALL BACKFILL AND FINAL GRADE ALL CUT OR FILL SLOPES TO MATCH EXISTING CONDITIONS TO THE SATISFACTION OF THE ENGINEER.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL CONSTRUCTION SURVEYING. ANY DEVIATIONS FROM EXISTING GRADES AS SHOWN ON THE PLANS SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER.
- 5. AREAS OF STOCKPILED MATERIALS WITHIN THE CONSTRUCTION AREA ARE TO BE TREATED IN SUCH A MANNER AS TO PREVENT MOVEMENT OR EROSION RESULTING FROM WIND CONDITIONS OR RAINFALL. THE CONTRACTOR IS TO SWEEP ON A DAILY BASIS ROADWAYS THAT ARE ALONG ITS ROUTES AND IMMEDIATELY CLEAN UP MUD THAT FALLS ON ANY PAVEMENT OUTSIDE OF ITS LIMITS OF CONSTRUCTION OR HAULING ACTIVITIES.
- 6. SOILS PREPARATION SHALL CONFORM TO THE REQUIREMENTS OF THE GEOTECHNICAL REPORT FOR FORMER THREE KIDS MINE SITE, CENTURY CONSULTANTS, JOB NUMBER 22004 AUGUST 19, 2022.
- 7. IMPERMEABLE LAYER CONSISTS OF SILT/CLAY MATERIAL WITH A PLACED PERMEABILITY OF NO GREATER THAN 1X10⁻⁵
- 8. FINAL DEPTHS AND ELEVATIONS TO BE PROPOSED BY CONTRACTOR AND APPROVED BY ENGINEER PRIOR TO PLACEMENT.





G-15,16,17 - HYDRO PIT LINER, FINAL GRADING PLAN, AND DETAILS - LINER DESIGN AND SUBDRAIN SYSTEM PROVIDED.





C 1 03/11/25 CAC ANCHOR TRENCH UPDA 2 06/27/25 CAC ANCHOR TRENCH UPDA 3 07/18/25 CAC ANCHOR TRENCH UPDA ANCH

921 AMERICAN PACIFIC DRIVE, SUITE 305 HENDERSON, NV 89014

8 WEST PACIFIC AVENUE ENDERSON, NEVADA, 89015 563-0600 (P) • (702) 563-0610 (F)

8 WEST HENDERSO (702) 563-0600

PROJECT NUMBER: 14-01-156

SCALE:

NTS

DESIGNED BY:

CAC DRAWN BY:

CHECKED BY:

CAC

/DRO PIT LINER
DETAILS
L DESIGN TO IMPLEME

HYDRO PIT

DETAIL

REMEDIAL DESIGN TO

CORRECTIVE ACT




FIGURE
G-17
17 OF 23 SHEETS

ATTACHMENT A

Responses to NDEP Comments made on June 30, 2025 to Modification No. 7 to the Remedial Design Report – Hydro Pit Liner, dated June 2, 2025

1. **General Comment #1** – Details 2 and 3 in Figure G-17 include the following text, respectively: "2.4' BELOW FINISHED GRADE OF LINER" and "2.4' BELOW FINISHED GRADE." These values should be updated to reflect the new elevations.

The values in Details 2 and 3 showing depth from ground surface to the bottom of the silt material are variable, depending on the thickness of cover placed in the new design. As a result, the text ""2.4' BELOW FINISHED GRADE OF LINER" and "2.4' BELOW FINISHED GRADE" were removed from the figure. Depths can be inferred from attachments GRD-1 and GRD-2. Additionally, a note was added indicated that final depths and elevations to be proposed by the contactor will be approved by an engineer.

2. Detail 3 in Figure G-17 includes an arrow labeled as "ZONE 1 MATERIAL," but the arrow is pointing to the gravel above the Zone 1 material. The arrow should be extended to point to the Zone 1 material.

Detail 3 in Figure G-17 was revised to extend the arrow labeling "ZONE 1 MATERIAL" to reach the intended layer.